


















DATA TEKNIS AIR COOLED SPLIT VRF

No.	LOKASI / RUANG YANG DILAYANI	JUMLAH UNIT	KODE UNIT		VOLUME UDARA		KAPASITAS PENDINGIN		EXT. STATIC PRESS. (Inch WG)	TEMP. UDARA		DIAMETER PIPA			DAYA LISTRIK				TINGKAT KEBISINGAN (dBA)	TIPE UNIT	KETERANGAN
			OUTDOOR	INDOOR	FRESH AIR (CFM)	SUPPLY (CFM)	TOTAL (BTU/H)	SENSIBEL (BTU/H)		MASUK (°F DB/WB)	KELUAR (°F DB/WB)	LIQUID (mm)	GAS (mm)	DRAIN (mm)	INDOOR UNIT (KW)	(V/Ph/Hz)	OUTDOOR UNIT (KW)	(V/Ph/Hz)			
01	LANTAI GROUND FLOOR		OU-01.01 346.000 BTU/H																		
	- LOBBY	3		IU-GF/LL.01~03	218	2.187	75.000	56.250	--	75,4/63,3	56,3/56,2	9,5	19,1	25	1,294	220/1/50	35,4	380/3/50	55	CEILING CONCEALED	
	- IT	1		IU-GF/IT.01	227	2.275	78.000	58.500	--	75,4/63,3	56,3/56,2	9,5	22,2	25	1,465	220/1/50			55	CEILING CONCEALED	
	- R. MEETING	1		IU-GF/RM.01	28	280	9.600	7.200	--	75,4/63,3	56,3/56,2	6,4	12,7	25	0,028	220/1/50			45	CASSETTE 4 WAY	
	- R. MEETING	1		IU-GF/RM.02	45	450	15.400	11.550	--	75,4/63,3	56,3/56,2	6,4	12,7	25	0,035	220/1/50			45	CASSETTE 4 WAY	
	- MDP ROOM	1		IU-GF/MDP.01	--	262	9.000	6.750	--	75,4/63,3	56,3/56,2	6,4	12,7	25	0,028	220/1/50			35	WALL MOUNTED	
	- FCC	1		IU-GF/FCC.01	--	262	9.000	6.750	--	75,4/63,3	56,3/56,2	6,4	12,7	25	0,028	220/1/50			35	WALL MOUNTED	
02	LANTAI 1		OU-01.01 154.500 BTU/H														13,9	380/3/50			
	- BACKSTAGE	1		IU-1/BS.01	78	787	27.000	20.250	--	75,4/63,3	56,3/56,2	9,5	15,9	25	0,092	220/1/50			45	CASSETTE 4 WAY	
	- LOUNGE	2		IU-1/L0.01~02	80	805	27.600	20.700	--	75,4/63,3	56,3/56,2	9,5	15,9	25	0,092	220/1/50			55	CEILING CONCEALED	
	- STUDIO	1		IU-1/S.01	--	262	9.000	6.750	--	75,4/63,3	56,3/56,2	6,4	12,7	25	0,028	220/1/50			35	WALL MOUNTED	
	- MEETING ROOM	1		IU-1/MR.01	--	373	12.800	9.600	--	75,4/63,3	56,3/56,2	6,4	12,7	25	0,033	220/1/50			35	WALL MOUNTED	
	- LOBBY LIFT	1		IU-1/LL.01	147	1.472	50.500	37.875	--	75,4/63,3	56,3/56,2	9,5	15,9	25	0,405	220/1/50			55	CEILING CONCEALED	
03	LANTAI 2		OU-02.01 370.000 BTU/H														36,7	380/3/50			
	SISTEM 1																				
	- AUDITORIUM	4		IU-2/ADR.01~04	270	2.697	92.500	69.375	--	75,4/63,3	56,3/56,2	9,5	22,2	25	1,465	220/1/50			55	CEILING CONCEALED	
	SISTEM 2																				
	- SMALL MEETING ROOM	1		IU-2/SMR.01	--	145	5.000	3.750	--	75,4/63,3	56,3/56,2	6,4	12,7	25	0,019	220/1/50	26,0	380/3/50	35	WALL MOUNTED	
	- QUITE ROOM	5	OU-02.02 255.100 BTU/H	IU-2/QR.01~05	--	145	5.000	3.750	--	75,4/63,3	56,3/56,2	6,4	12,7	25	0,019	220/1/50			35	WALL MOUNTED	
	- LARGE MEETING ROOM	1		IU-2/LMR.01	110	1.096	37.600	28.200	--	75,4/63,3	56,3/56,2	9,5	15,9	25	0,144	220/1/50			45	CASSETTE 4 WAY	
	- LOBBY LIFT	3		IU-2/LL.01~03	182	1.822	62.500	46.875	--	75,4/63,3	56,3/56,2	9,5	15,9	25	1,294	220/1/50			55	CEILING CONCEALED	
04	LANTAI 3		OU-03.01 297.300 BTU/H														33,0	380/3/50			
	- SMALL MEETING ROOM	1		IU-3/SMR.01	--	145	5.000	3.750	--	75,4/63,3	56,3/56,2	6,4	12,7	25	0,019	220/1/50			35	WALL MOUNTED	
	- R. KERJA STAFF	3		IU-3/RKS.01~03	247	2.479	85.000	63.750	--	75,4/63,3	56,3/56,2	9,5	22,2	25	1,465	220/1/50			55	CEILING CONCEALED	
	- MUSHOLLA	1		IU-3/MS.01	--	364	12.500	9.375	--	75,4/63,3	56,3/56,2	6,4	12,7	25	0,030	220/1/50			35	WALL MOUNTED	
	- MEDIUM MEETING ROOM	1		IU-3/MMR.01	--	280	9.600	7.200	--	75,4/63,3	56,3/56,2	6,4	12,7	25	0,028	220/1/50			35	WALL MOUNTED	
	- MEETING ROOM	1		IU-3/RM.01	--	443	15.200	11.400	--	75,4/63,3	56,3/56,2	6,4	12,7	25	0,028	220/1/50			35	WALL MOUNTED	
05	LANTAI 3A		OU-03A.01 233.300 BTU/H														26,0	380/3/50			
	- R. KERJA DIREKTUR	1		IU-3A/RKD.01	--	145	5.000	3.750	--	75,4/63,3	56,3/56,2	6,4	12,7	25	0,028	220/1/50			35	WALL MOUNTED	
		2		IU-3A/RKD.02~03	--	306	10.500	7.875	--	75,4/63,3	56,3/56,2	6,4	12,7	25	0,030	220/1/50			35	WALL MOUNTED	
		2		IU-3A/RKD.04~05	--	280	9.600	7.200	--	75,4/63,3	56,3/56,2	6,4	12,7	25	0,028	220/1/50			35	WALL MOUNTED	
		1		IU-3A/RKD.06	--	373	12.800	9.600	--	75,4/63,3	56,3/56,2	6,4	12,7	25	0,030	220/1/50			35	WALL MOUNTED	
		1		IU-3A/RKD.07	--	373	12.800	9.600	--	75,4/63,3	56,3/56,2	6,4	12,7	25	0,035	220/1/50			45	CASSETTE 4 WAY	
	- LARGE MEETING ROOM	1		IU-3A/LMR.01	90	889	30.500	11.625	--	75,4/63,3	56,3/56,2	9,5	15,9	25	0,092	220/1/50			45	CASSETTE 4 WAY	
	- LOBBY LIFT	2		IU-3A/LL.01~02	192	1.925	66.000	49.500	--	75,4/63,3	56,3/56,2	9,5	15,9	25	1,294	220/1/50			55	CEILING CONCEALED	

OWNER/CLIENT  APPROVED : .../.../...  ..... (name) ..... (position) ..... (Dep./Div.) (signed)	PROJECT  BPDP KELAPA SAWIT  Jl.Medan Merdeka Tim, RT.7/RW.1, Gambir, Kec. Gambir, Kota Jakarta Pusat, Daerah Khusus Ibukota Jakarta 10110	INTERIOR DESIGN CONSULTANT  PT. MADEA AGKASAMA Jl. Heli Suci No. 4 Gd. Sakura Lt. 2 Room 201 Kel. Kampung Bali, Kec. Tanah Abang, Jakarta Pusat Telp. 021 - 2303483 , Fax. 021 - 2303483 APPROVED : //	MEP CONSULTANT   PT. DUTA PRATAMA ENGINEERING MECHANICAL & ELECTRICAL ENGINEER Rukan Taman Murya Blok M No. 37, J. Batu Mulia No. 1 Murya Utara Kemang - Jakarta Barat 11620 Phone : 021-5845546, 5845547, 5845556, Fax : 021-58474631 Email : dpape@gnsl.com, pt.dpa.me@yahoo.com	DRAWING TITLE  DATA PERALATAN LEMBAR 1  SCALE : NTS  ALL MEASUREMENT MUST BE CHECKED AT BY SITE BY THE CONTRACTORS AND ANY DIFFERENCES REPORTED/INITIATED TO THE DESIGNER FOR CLARIFICATION BEFORE PROCEEDING.	<table><tr><td></td><td></td><td>.../.../...</td></tr><tr><td></td><td></td><td>.../.../...</td></tr><tr><td></td><td></td><td>.../.../...</td></tr><tr><td></td><td></td><td>.../.../...</td></tr><tr><td></td><td></td><td>.../.../...</td></tr><tr><td>#</td><td>REVISION :</td><td>DATE</td></tr></table>			.../.../...			.../.../...			.../.../...			.../.../...			.../.../...	#	REVISION :	DATE	DRAWN Iqbal DATE : 15/05/24  CHECKED Dhono DATE : 15/05/24  DRAWING FOR	DRAWING NUMBER VAC-003  PAGE   TENDER
		.../.../...																							
		.../.../...																							
		.../.../...																							
		.../.../...																							
		.../.../...																							
#	REVISION :	DATE																							